

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24963-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 18-20S-12W
1150 feet from S Section Line, 1150 feet from E Section Line
Lease Name: ROSE Well #: 1-18
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	314	0	300 SX CMT.
T1	2.375	3450		
PKR		3454		
PROD	5.5	3599	2200	150 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2011 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES, SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2200' - pulled casing to 1550' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 700' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 315' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 150' - circulated cement with 50 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3470	3474		
3459	3461		

RECEIVED
SEP 09 2011
KCC WICHITA

Remarks: QUALITY WELL SERVICE.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

SEP 02 2011

Form CP-2/3
9/13/11