

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07280-00-00
Spot: SESENW Sec/Twnshp/Rge: 12-18S-11W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MUELLER Well #: 1
County: BARTON Total Vertical Depth: 3282 feet

Operator License No.: 31561
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM
Address: 410 B ST PO BOX 531
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	234	0	w/155 sxs cmt
PROD	5.5	3279	1195	w/75 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: C&K OIL COMPANY Phone: (620) 786-8744

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 1195' - pulled casing to 1190' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 600' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 300' - circulated cement with 100 sxs cement.
Pulled casing - hole stayed full.

RECEIVED
SEP 09 2011
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

9/13/11

SEP 02 2011