

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00387-00-02
Spot: W2SESESW Sec/Twnshp/Rge: 24-10S-21W
299 feet from S Section Line, 3063 feet from E Section Line
Lease Name: ACHESON Well #: 1
County: GRAHAM Total Vertical Depth: 3825 feet

Operator License No.: 31822
Op Name: JOLEN OPERATING COMPANY
Address: 100 N BROADWAY AVE STE 2460
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3710		
SURF	8.625	226	0	175 SX
PROD	5.5	3769	0	125 SX

Well-Type: EOR UIC Docket No: E26188.1 Date/Time to Plug: 08/25/2011 11:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: PERRY S. HENMAN Company: JOLEN OPERATING COMPANY Phone: (405) 235-8444

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls - 14 sxs gel.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2011 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3380' - pumped 14 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1800' - pumped 155 sxs cement with 200# hulls.
Pulled tubing out. Topped off with 25 sxs cement - full.
Tied onto backside - pumped 2 sxs cement.
S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3482	3625		LANSING

RECEIVED
SEP 09 2011
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #20331.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

Form CP-2/3

AUG 26 2011

OK to MC 9/09/11
9/13/11