

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-21025-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 5-14S-32W
2033 feet from N Section Line, 1926 feet from E Section Line
Lease Name: BERKGREN Well #: 2
County: LOGAN Total Vertical Depth: 4575 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/02/2011 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: BLAKE EXPLORATION, LLC Phone: (785) 421-2921

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 09/02/2011 7:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st. Plug at 2270' w/25 sxs.
2nd. Plug at 1240' w/100 sxs.
3rd. Plug at 273' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: S.O.S. CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED

SEP 12 2011

KCC WICHITA

Form CP-2/3

9/12/11

SEP 08 2011