

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20430-00-00
Spot: SWSENE Sec/Twnshp/Rge: 23-10S-15W
1275 feet from N Section Line, 515 feet from E Section Line
Lease Name: RUGGLES A Well #: 1
County: OSBORNE Total Vertical Depth: 3700 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/01/2011 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: TOM ALM Company: BRUNGARDT OIL AND LEASING I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 09/01/2011 8:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 3589' w/25 sxs.
2nd. Plug at 1100' w/25 sxs.
3rd. Plug at 650' w/100 sxs.
4th. Plug at 275' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

RECEIVED Form CP-2/3
SEP 12 2011 9/13/11

SEP 08 2011

KCC WICHITA