

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22556-00-00
Spot: NESENWSW Sec/Twnshp/Rge: 18-12S-21W
1972 feet from S Section Line, 1190 feet from W Section Line
Lease Name: DORZWEILER FAMILY TRUS Well #: 1
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		
SURF	8.625	217	0	150 SX CMT
T1	2.875	3500		
PC		1724		400 SX CMT
PROD	5.5	4018	0	165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/06/2011 11:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: JOHN FOSE Company: CMX, INC. Phone: (785) 743-2388

Proposed Plugging Method: Ordered 355 sxs 60/40 pozmix - 4% gel - 600# hulls - 5 sxs gel.
Perf: 2200' - 1750'.
PC at 3496'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/06/2011 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3495' - pumped 5 sxs gel - followed with 75 sxs cement with 200# hulls mixed in.
Pulled tubing to 2261' - pumped 100 sxs cement with 200# hulls mixed in.
Pulled tubing to 1227' - pumped 105 sxs cement with 200# hulls mixed in - lose circulated.
Pulled tubing to 600' - pumped 35 sxs cement and regained circulation.
POOH. Topped casing off with 15 sxs cement - hole stayed full.
Braden head was found to be full of cement.

Perfs:

Top	Bot	Thru	Comments
3736	3745		
3656	3660		
3622	3625		

Remarks: QUALITY OIL WELL SERVICE-TICKET #5291.

Plugged through: TBG

District: 04

Signed

Ray A. D. K.

(TECHNICIAN)
RECEIVED

SEP 12 2011

KCC WICHITA

Form CP-2/3

9/13/11

SEP 08 2011