

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20564-00-00
Spot: E2SW Sec/Twnshp/Rge: 15-18S-32W
1125 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: FRANCE A Well Number: 1
County: SCOTT Total Vertical Depth: 4685 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 271
Production: Size feet:
Liner: Size feet:

8152.26

Well Type: DH UIC Docket No: Date/Time to Plug: 08/17/2001 7:15 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2330' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/17/2001 9:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

1ST PLUG AT 2330' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

RECEIVED
9-6-01
SEP 06 2001
KCC WICHITA

INVOICED
DATE 9-6-01
INV. NO. 2002060357

AUG 23 2001

Form PF-3