

1 060555

API NUMBER 15-171-20,236-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NE NW, SEC. 26, T 18 S, R 32 W ~~E~~
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5053 ~~4049 (Dynasty Drilg. Corp.)~~ Lease Name Beckley Well # 1

Operator: Petro-Dynamics Corp. County Scott 151.71

Name & Address 1650 Georgetown, Suite 200 Well Total Depth 4668 feet

Wichita, KS 67208 Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108, Geneseo, KS 67444

Company to plug at: Hour 10:00 pm Day: 27 Month: April Year: 1985

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: 4 1/2" at 4668' Opens Hole 4560-560'

1st plug sand back to 4560' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:45 pm Day: 27 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4560' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 800 psi and shut in 100 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(if additional description is necessary, use BACK of this report)

MAY 02 1985
52-85
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(copy of report) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 5-7-85

8024