



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973
2-26-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petr., Inc., has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling & Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Beckley Well No. 2

Location: SE-NE-NE Sec. 13 Twp. 18 Rge. (E)(W) 32

County: Scott Total Depth 4597' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

610'--8 5/8" Surface casing, cement circulated w/450 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft. cement thru DP. Pull DP to 620' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls add 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent