



15-171-20038-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1972
5-24-72
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. E. Smith of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc., & Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Beckley Well No. E-1

Location: NE-SW-SE Sec. 26 Twp. 18 Rge. (E)(W) 32

County: Scott Total Depth 4693' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Smith was instructed to plug the well as follows:

661'--8 5/8" Surface casing, cement circulated with 400 Sx.

Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 700' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent