



15-171-0002-1-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

8-18-69
AUG 18 1969

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Company, has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply Company, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Newby Well No. B-2

Location: CNE-SW Sec. 23 Twp. 18 Rge. (E)(W) 32

County: Scott Total Depth 4740' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

306'--8 5/8" Surface casing, cement circulated with 275 Sx.
4739'--5 1/2" Production casing cemented on bottom with 225 Sx. Top perforations 3961' to 3966'. No plug back shown.

Push plug to 3800', sand to 3750' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 1250' and circulate heavy gel mud then displace 100 Sx. cement thru 5 1/2" @ 1250'. Pull 5 1/2" to 350' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" casing, set rock bridge @ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent