



15:17:20011-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 16 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Dale Oller of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company,

Complete Address: P. O. Box #2585, Amarillo, Texas.

Lease Name: Wright Well No. 1

Location: CNW-SE Sec. 32 Twp. 18 Rge. (E)(W) 32

County: Scott Total Depth 4750' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

335'--85/8" Surface casing, cement circulated with 280 Sx.
Dakota Section Top @1025'.

Circulate hole with heavy mud, Pull DP to 1285' and displace 100 Sx.
cement thru DP. Pull DP to 360' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

N. D. Fischele
 Conservation Division Agent