



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1972
7-26-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co. Inc has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Strickert Well No. 1

Location: SE-NE-SW Sec. 36 Twp. 18 Rge. (E)(W) 32

County: Scott Total Depth 4730' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Voth was instructed to plug the well as follows:

668'--8 5/8" Surface casing, cement circulated with 400 Sx.
3022'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of
cement @ 2416 (Temp. Survey). Well plugged back to 2810'. Top of per-
forations @ 2770'.

Sand well back to 2750' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hull, 35 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent