

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 1516919059-0000

LEASE NAME Gustafson

WELL NUMBER 1 SWD

SPOT LOCATION C SE

SEC. 25 TWP. 15 RGE. 4 (R) or (W)

COUNTY Saline

Date Well Completed 3/55

Plugging Commenced 7/24/84

Plugging Completed 7/24/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 300 Sutton Place, Wichita, KS 67202

PHONE # (316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well SWD & Water supply  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? - If not, is well log attached? yes

Producing formation - - Depth to top - bottom - T.D. 274

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand	water	250	280	10 3/4	120	None
				7	248	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Run tubing to 280' and pump 60 sx 50/50 poz. Pull tubing and let set. Pump 60 sx 50/50 poz down casing to completely fill hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc./Allied Cementing License No. \_\_\_\_\_

Address Allied - Box 31

Russell, KS

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher, Drilling & Production Manager (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher

(Address) 300 Sutton Place



SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 84

Helen L. Coyer  
Helen L. Coyer  
Notary Public

My Commission expires: April 1, 1986

15169-19059-0000

Sec 25-15S-4W

C-4310

WELL LOG

REPUBLIC NATURAL GAS COMPANY  
Gustafson S.W.D. #1

Smolan Pool, Saline Co., Kansas  
TD 274', Comm. 1-22-55, Comp. 1-27-55

Figures Indicate Bottom of Formation

Soil	4'
Clay	40'
Sand	50'
Shale and Shells	210'
Shale	249'
Sand	274' T.D.

10-3/4" O.D. surface casing set at 120' and cemented with 130 sacks--cement circulated to surface. 7" O.D. casing set at 248' and cemented with 100 sacks. Input test indicated well was taking water at a rate of 150 B/Hr. Cement circulated to surface around 7" casing. Completed for Salt Water Disposal

SIGNED




District Engineer

Subscribed and sworn to before me this 28th day of March, 1955

My Commission expires - 8-20-55

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1984



Yvonne M. Stevenson  
Notary Public

CONSERVATION DIVISION  
Wichita, Kansas