


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C W/2 E/2 SE/4
Lease Owner Fender Pipe & Supply, Inc.
Lease Name Liljestrand Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-9-66 _____ 19____
Plugging completed 5-11-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	346'	None
				5-1/2"	3439'	2850'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3440', sanded to 3430' and dumped 5 sacks of cement @ 3430' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 260' to 250' and dumped 20 sacks of cement @ 250'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1966
5-24-66

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight

(employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 66

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

15-169-00500-0000

WELL LOG

DERBY OIL COMPANY
Liljestrand #4

C W/2 E/2 SE/4
Sec. 35, Twp. 15, Rge. 4
Saline County, Kansas

Total Depth: 3440'
Commenced: June 28, 1954
Completed: July 13, 1954
Drilled by Shields Drilling Co., Inc.

CASING RECORD

Size	Run	Cemented	Elevation: 1327' RB
8 5/8"	346'	Cmtd. with 250 sax	Treatment:
5 1/2"	3439'	Cmtd. with 100 sax	Production

-----Figures indicate Bottom of Formation-----

Surface Clay	20
Sand	45
Blue Shale	85
Shale & Shells	335
Anhydrite	390
Lime	475
Lime & Shale	615
Shale & Lime	740
Lime & Shale	1210
Shale & Salt	1450
Shale	1645
Lime & Shale	2145
Lime	2275
Lime & Shale	2345
Shale & Lime	2455
Lime	2505
Shale & Lime	2585
Lime & Shale	2914
Lime	2944
Lime & Shale	3028
Lime	3132
Lime & Shale	3224
Shale & Lime	3282
Lime & Shale	3330
Shale	3439
Maquoketa	3440 TD

TOPS

Maquoketa Dolomite 3439'

RECORDED
 STATE DEPARTMENT OF REVENUE
 JUL 18 - 1954
 COMMISSIONER OF REVENUE
 Topeka, Kansas