


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Map Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 35 Twp. 16 Rge. 4 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. SE SW SE
Lease Owner American Petrofina Company of Texas
Lease Name Larson Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-1-65 19
Plugging completed 2-5-65 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3444 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	352'	None
				5-1/2"	3441'	2880'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3444', sanded to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, checked fluid to 200', set rock bridge to 190' and dumped 20 sacks of cement @ 190'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1965
2-15-65
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE ss.
Noel J. Knight (employee of owner) or (owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of February, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.

STERLING DRILLING CO.

STERLING, KANSAS

WELL LOG LARSON #1

Location - SE/4 SW/4 SE/4 of Section 35-153-14, Saline County, Kansas

Owner - The El Dorado Refining Company
Rotary Drilling Contractor - Sterling Drilling Company
Cable Tools Contractor -

Commenced - 7-15-51
Completed - 7-30-51 (w/r)
" " 8-6-51 (w/c.t.)

Total Depth - 3441' (w/r)
" " 3435' (w/c.t.)

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1964

CONSERVATION DIVISION
Wichita, Kansas

COPY

LOG

0- 95	Surface Clay and Shale
95- 295	Sand and Shale
295- 355	Shale
355- 375	Shale and Shells
375- 390	Anhydrite
390- 530	Shale, Sand and Lime
530- 755	Lime and Shale
755- 945	Lime
945-1845	Lime and Shale
1845-2120	Lime
2120-2310	Shale and Lime
2310-2470	Lime
2470-2520	Shale and Lime
2520-2650	Lime
2650-2740	Shale
2740-2785	Shale and Lime
2785-2955	Shale
2955-3200	Lime
3200-3235	Lime and Shale
3235-3440	Shale
3440-3435	Lime

CASING RECORD

352' of 8-5/8" Surface Pipe
Cemented with 100 Sacks Cement
through the pipe, and 95 Sacks Cement
on the outside of pipe

3441' of 5 1/2" Casing
Cemented with 75 Sacks Cement

Corrected TD 3' down SLM, Drilled
plug and CO to TD, 2850' oil in hol
in 24 hrs, 11 BO & 1 BW per hrs.
test. Run tubing and rods.