


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW&SW&" or footage from lines Saline County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)
Lease Owner American Petrofina Company of Texas
Lease Name Larson Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-21-65 _____ 19____
Plugging completed 1-25-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3427 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	378'	None
				8-5/8"	378'	
				5-1/2"	3425'	2787'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3427', sanded to 3405' and dumped 5 sacks of cement @ 3405' with dump bailer. Pulled 5 1/2" casing, checked fluid to 300', set rock bridge to 290' and dumped 20 sacks of cement @ 290' with dump bailer. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1965
2-2-65

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of January, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.

WELL LOG - - - - -

Located: NE 1/4 SE Sec. 39-15-4N,
Saline County, Kansas.

OWNER: El Dorado Refining Company
 DRILLING CONTRACTOR: Sterling Drilling Company
 CABLE TOOL CONTRACTOR:

RECEIVED
 STATE CORPORATION COMMISSION

DEC 23 1964

CONSERVATION DIVISION
 Wichita, Kansas

Completed: 3-21-54 (w.r.)
 (w.c.t.)
 Completed: 4-2-54 (w.r.)
 (w.c.t.)

Total Depth: 3430'

LOG

0- 50	Clay & Sand
50-1140	Lime
1140-1690	Shale
1690-2040	Lime
2040-2240	Lime & Shale
2240-2770	Lime
2770-2970	Lime & Shale
2970-3075	Lime & Chert
3075-3200	Lime
3200-3350	Shale
3350-3370	Lime
3370-3425	Lime & Shale
3425-3430	Lime

CASING RECORD

Run 378' of 4-5/8" casing, cemented
 with 250 sacks of cement.

Run 3433.35' of 5-1/2" casing, cemented
 with 75 sacks of cement.