

15.169.00854.0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Salina County. Sec. 26 Twp. 15 Rge. 4 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 SW/4 SE/4  
Lease Owner Republic Natural Gas Company  
Lease Name Swenson Well No. 2  
Office Address Box 126, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed December 29 19 51  
Application for plugging filed April 13 19 59  
Application for plugging approved April 14 19 59  
Plugging commenced May 12 19 59  
Plugging completed May 14 19 59  
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production October 19 53  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman  
Producing formation Maquoketa Depth to top 3422 Bottom Total Depth of Well 3423 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	315'	None
				5-1/2"	3422'	2881'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Run 5 sks. cement at 3423'  
Mud to 310' & make solid with rock bridge  
Run 20 sks. cement  
Mud to 40' & make solid with rock bridge  
Run cement to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service  
Address 102 West Eighteenth, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
P. B. Horst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P.B. Horst  
Box 126, Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 19 59

My commission expires 8-20-59

Yvonne M. Stinson  
Notary Public.



PLUGGING  
FILE SEC OCT 15 RALW  
BOOK PAGE 29 LINE 27

RECEIVED  
STATE CORPORATION COMMISSION  
6-1-59  
JUN 1 1959

CONSERVATION DIVISION  
Wichita, Kansas

C  
O  
P  
Y

E. K. Carey, Contractor - Operator  
Box 620  
McPherson, Kansas

Tillie Swenson #2

SE SW SE  
Sec. 26-15S-4W  
Saline County, Kansas

Commenced: 12- 6-51  
Completed: 12-19-51

Elevation: 1398 K. B.

8-5/8" x 5 1/2" Head 6.45'  
below K. B.

Casing Record:

8-5/8" 315' w/250 sacks

5-1/2" 3422' w/75 sacks

Contractor: E. K. Carey, Contractor (Rig #2) Box 620, McPherson, Kansas  
Geologist: Don Hollar, E. K. Carey Drlg. Co. 815 Central Bldg. Wichita, Ks.

Figures Indicate Bottom of Formation K. B.

Cellar	7
Clay	17
Sand	22
Shale	42
Sand	50
Shale & shells	150
Lime & shale	195
Lime	315
Lime & shale	530
Lime & shale	770
Lime	935
Shale & lime	1765
Lime & shale	2045
Shale & lime	2256
Lime	2617
Shale & lime	2888
Shale	2905
Lime	3184
Shale	3215
Shale & lime	3280
Shale & shells	3358
Shale	3422
Lime	3423

**RECEIVED**  
STATE CORPORATION COMMISSIONER

APR 14 1950

Geologist Tops:

Mississippi	2912
Kinderhook	3182
Hunton	3338
Maquoketa Sh.	3350
Maquoketa Dol.	3422 *2114
Rotary Total Depth	3423 -2115

Set 5 1/2" @ 3422'

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. CAREY, CONTRACTOR

/s/ Herbert Rhoton

By Herbert Rhoton, Supt.

PLUGGING			
FILE	SEC. 26	T. 15	R. 4W
BOOK	PAGE 29	LINE 27	