

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines C W/2 W/2 SE/4

Lease Owner American Petrofina Company of Texas

Lease Name Larson Well No. 3

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 1-28-65 19

Plugging completed 1-30-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3423 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	357'	None
				5-1/2"	3422'	3021'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3423', sanded hole to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, checked fluid to 300', set rock bridge to 290' and dumped 20 sacks of cement @ 290'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1965

2-9-65

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1965

My commission expires May 20, 1968 Notary Public.

THE EL DORADO REFINING CO.
Larson #3

W/2 W/2 SE
Sec. 35, Twp. 15S, Rge. 4W
Saline County, Kansas

T. D.: 3423
Commenced: June 21, 1952
Completed: July 3, 1952 7-3-52 w/ C.T.
Drilled by Shields Drilling Co., Inc.

FORMATION TOPS: D. F.

Miss. 2912
Kind. 3187
Mq. sh. 3356
Mq. dol. 3419

Elevation: 1313 D. F.
Treatment:
Production: 140 BOPD, N. W.

CASING RECORD

Size	Run	
12-3/4"	68'	Pulled
8-5/8"	357.11'	Cemented (300 sax)
5-1/2"	3422'	Cemented (60 sax)

	From	To
Surface & Shale	0	106
Shale & Chip	106	300
Chip & Anhydrite	300	354
Run 11 jts. of 8-5/8" new seamless surface pipe; measures 357.11'; set at 351' and cemented with 300 sax of cement		
Anhydrite & Lime	354	410
Lime & Sand	410	640
Sand, & Shale, Broken	640	770
Shale & Lime	770	821
Lime & Shale	821	920
Lime, Shale & Salt	920	1175
Shale, Shells, & Salt	1175	1475
Shale & Shells, Lime-Broken	1475	1760
Shale & Lime	1760	1890
Lime & Shale	1890	1995
Lime & Shale	1995	2145
Lime & Shale	2145	2265
Shale & Lime	2265	2330
Lime	2330	2455
Lime & Shale Streaks	2455	2525
Lime & Shale	2525	2575
Lime & Shale	2575	2665
Lime & Shale	2665	2760
Lime & Shale	2760	2845
Shale	2845	2909
Lime & Shale	2909	2971
Lime & Shale	2971	3010
Lime & Shale	3010	3057
Lime, Shells, & Shale	3057	3117
Cherty Lime & Shale	3117	3142
Lime & Shale	3142	3186
Lime & Shale	3186	3250
Shale	3250	3330
Shale	3330	3394
Shale	3394	3423 T. D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1964
CONSERVATION DIVISION
Wichita, Kansas

D. P. & C. O. to 3420, T.D. D. F., 75' OIH; D. S. 3421: 125' OIH/ 3/4 hrs.
250' OIH/1 hr; F.U. 2000' OIH/16 hrs. # 57 BO/16 hrs.