


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

SALINE County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)
Location as "NE/CNW/SW" or footage from lines E $\frac{1}{2}$ SW/4
Lease Owner Shields Oil Producers
Lease Name Shields Oil Producers-Valen Well No. 1
Office Address Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed March 20 19 52
Application for plugging filed June 1 19 57
Application for plugging approved June 3 19 57
Plugging commenced June 4 19 57
Plugging completed June 8 19 57
Reason for abandonment of well or producing formation Depleted well

If a producing well is abandoned, date of last production June 1 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Rule Durkey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3432 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	378	cmtd w/300 sax
				5 1/2"	3423 1/2	2970 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3432 feet to surface feet for each plug set.

Hole filled with sand from 3432 to 3410; six sacks of cement placed in hole with dump bailer; hole filled with mud to 200 ft; ten foot rock bridge installed betw en 200 ft to 90 ft; fifteen sacks of cement then poured in hole and hole filled with mud to 20 ft; five foot rock bridge installed between 20 and 15 feet, and hole capped with five sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,
Address Russell, Kansas.

STATE OF Kansas COUNTY OF Russell, ss.
R. J. Shields (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) RJ Shields

Shields Building - Russell, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 17th day of June, 19 57
December 18, 1957

John R. Bivins
STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC. 35 T. 15 R. 4W
BOOK PAGE 16 LINE 27

JUN 19 1957
6-19-57
CONSERVATION DIVISION
Wichita, Kansas

15-169-00867-0000

WELL LOG

SHIELDS OIL PRODUCERS
Valin #1

E/2 E/2 SW
Sec. 35, Twp. 15S, Rge. 4W
Saline County, Kansas

Total Depth: 3424'
Commenced: March 7, 1952
Completed: March 20, 1952
Drilled by Shields Drilling Co., Inc.

CASING RECORD

Size	Run	
8-5/8"	378'	Cemented (300 sax)
5-1/2"	3423-1/2	Cemented (50 sax)

Elevation: 1315' RB
Treatment: None
Production: Swb 5.4 BOPH/14 hrs.
No water.

	From	To
Surface & Sand	0	68
Shale & Shells	68	315
Shale & Shells	315	375
Anhydrite	375	378
Anhydrite	378	434
Broken Anhydrite	434	460
Shale & Lime	460	565
Lime & Shale	565	715
Shale & Shells	715	735
Shale & Red Bed	735	805
Lime & Shale	805	865
Lime & Shale	865	1070
Lime & Shale & Salt	1070	1275
Salt & Shale	1275	1310
Lime & Shale	1310	1470
Shale	1470	1645
Shale & Lime	1645	1819
Shale & Lime	1819	1975
Lime	1975	2075
Shale	2075	2200
Lime & Shale	2200	2330
Lime	2330	2455
Shale & Lime	2455	2505
Lime & Shale	2505	2620
Lime & Shale	2620	2720
Lime & Shale	2720	2790
Shale & Lime	2790	2838
Shale	2838	2890
Shale - Broken	2890	2930
Shale & Lime	2930	2942
Lime & Shale	2942	3003
Lime & Shale	3003	3068
Lime & Shale	3068	3090
Lime	2090	3130
Lime	3130	3147
Shale & Broken Lime	3147	3165
Lime & Shale	3165	3205
Shale & Lime	3205	3268
Shale	3268	3357
Shale	3357	3415
Shale	3415	3424 TD

RECEIVED
COMMISSION
JUN 3 X 1957
CONSERVATION DIVISION
Wichita, Kansas

NOTES

Tops: Miss. 2899'
Hunt. 3351'
Maq. 3363'
Maq. Dol. 3423'

Note: Rework - DD to 3432'

PLUGGING
FILE SEC 35 T. 15 R. 4W
BOOK PAGE 16 LINE 27