

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Saline County. Sec. 35 Twp. 15 Rge. 4 (E)W (W)

Location as "NE/CNW%SW%" or footage from lines SW SE SE

Lease Owner Fender Pipe & Supply, Inc.

Lease Name Liljestrand Well No. 2

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5-14-66 19

Plugging completed 5-17-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3461 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	345'	None
				4-1/2"	3449'	2957'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, pushed plug to 3430', sanded to 3420' and dumped 3 sacks of cement @ 3420' with dump bailer. Pulled 4 1/2" casing, set rock bridge from 260' to 250' and dumped 20 sacks of cement @ 250'. Mudded hole to 30', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1966  
S. 24-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

SUBSCRIBED AND SWORN to before me this 21st day of May, 1966

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

ROTARY DRILLER'S LOG

15169-00498-0000

Derby Oil Company - Operator  
 Box 1030  
 Wichita, Kansas

1325 KB  
 Elevation: 1322 DF

Top 3-5/8" x 4 1/2" Head 6.65'  
 below K. B.

Liljestrand #2

SW 1/4, SE 1/4, SE 1/4  
 Sec. 35-15S-4W  
 Saline County, Kansas

Casing Record:  
 3-5/8", 345' cemented  
 with 168 sacks

4 1/2", 3450' cemented with  
 75 sacks.

Well Commenced: 8- 3-51  
 Well Completed: 8-21-51

Contractor: E. K. Carey, Contractor (Rig #1) Box 620, McPherson, Kansas  
 Geologist: Don Moller, with Derby Oil Company, Box 1030, Wichita, Kansas

Figures indicate bottom of formation K.B.

Rotary base & cellar	8	Lime	2480
Shale	20	Lime	2580
Shale	65	Lime	2660
Sand	75	Lime & shale	2715
Shale & shells	265	Lime & shale	2780
Sand	275	Shale & lime	2880
Shale & lime	340	Shale	2915
Lime	345	Lime	2940
Shale & shells	370	Lime	2984
Lime	475	Lime	3026
Lime	658	Lime	3066
Lime	765	Lime	3116
Lime & shale	830	Lime	3128
Lime & shale	935	Lime	3154
Shale Lime	1365	Lime	3184
Shale & lime	1725	Lime	3198
Shale & lime	1800	Shale	3258
Lime & shale	1850	Shale	3336
Lime	1975	Shale & lime	3388
Lime	2075	Shale	3432
Lime & shale	2160	Lime	3435
Lime shale	2295	Lime	3450 TD
Lime	2320		
Lime	2430		

RECEIVED  
 MAY 15 - 1956  
 DON MOLLER  
 WICHITA, KANSAS

Geologist Taps:

Maquoketa Dolomite 3432 (-2107)  
 Oil show 3432 - 42  
 Total Depth 3450'

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

E. K. Carey, Contractor

*Herbert Rhoton*  
 By Herbert Rhoton, Supt.