

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Saline County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines C E/2 W/2 SE/4
Lease Owner American Petrofina Company of Texas
Lease Name Larson Well No. 5
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-26-65 19
Plugging completed 1-28-65 19
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	875'	None
				5-1/2"	3428'	2893'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3430', sanded to 3400' and dumped 5 sacks of cement @ 3400' with dump bailer. Pulled 5 1/2" casing, checked fluid to 280', set rock bridge to 270' and dumped 20 sacks of cement @ 270'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

FEB 9 1965
2-9-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
Noel J. Knight

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1965

Milton J. Volin

My commission expires May 20, 1968

Notary Public.

15-169-00863-0000

-LAWSON 09

WELL LOG

Located: C 1/2 W/2 SE Sec. 35-15-01
Saline County, Kansas.

OWNER: The El Dorado Refining Company
EDTARY DRILLING CONTRACTOR: Sterling Drilling Company
CABLE TOOL CONTRACTOR:

Commenced: 4-3-54 (w.r.)
(w.c.t.)

Completed: 4-15-54 (w.r.)
(w.c.t.)

Total Depth: 3437'

LOG

0- 230	Sand & Shale
230- 370	Shale & Shells
370-1035	Lime
1035-1150	Lime & Shale
1150-1820	Shale
1820-2050	Lime
2050-2200	Lime & Shale
2200-2360	Lime
2360-2450	Shale
2450-2700	Lime
2700-2880	Shale & Lime
2880-2910	Shale
2910-2975	Lime
2975-3170	Lime
3170-3275	Shale
3275-3425	Shale & Lime
3425-3437	Lime

CASING RECORD

Ran 8-5/8" casing to 375', cemented with
290 sacks of cement.

Ran 3 1/2" casing to 3448.76', cemented
with 75 sacks of cement.

PRODUCTION

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1964

CONSERVATION DIVISION
Wichita, Kansas