

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline

County. Sec. 35 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 SW/4

Lease Owner Shields Oil Producers.

Lease Name Shields Oil Producers-Valen Well No. 2.

Office Address Russell, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed May 12 19 52

Application for plugging filed June 1 19 57

Application for plugging approved June 3 19 57

Plugging commenced June 10 19 57

Plugging completed June 13 19 57

Reason for abandonment of well or producing formation Depleted well

If a producing well is abandoned, date of last production June 1 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Rule Durkey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3441 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	344	cmtd w/300 sax
				5 1/2"	3433 1/2	2972 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3441 feet to Surface feet for each plug set.

Hole filled with sand from 3441 to 3415; Six sacks of cement placed in hole with dump bailer; hole filled with mud to 200 ft; ~~XXXXXX~~ rock bridge installed at 200 ft and fifteen sacks of cement poured in hole; hole filled with mud to 20 ft; rock bridge installed and hole capped with five sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Pulling Co.,

Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. J. Shields*


Shields Building - Russell, Kansas

(Address) 57

SUBSCRIBED AND SWORN to before me this 17th day of June, 19 57

My commission expires December 18, 1957

Jack P. Boerman
STATE CORPORATION COMMISSION Notary Public.



WELL LOG

SHIELDS OIL PRODUCERS

Valin #2

SE SE SW

Section 35-15-4

Saline County, Kansas

T.D.: 3435'
 Commenced: April 29, 1952
 Completed: May 12, 1954
 Contractor: Shields Drilling Co., Inc.

CASING RECORD

Size	Run	Pulled	Elevation: 1324 R.E.
8 5/8"	344'	Cemented w/ 300 sax	Treatment: Natural
5 1/2"	3433 1/2'	Cemented (50 sax)	Production: Swab 2 1/2 BOPH No water. Pot. 25 BOPD

Figures Indicate Bottom of Formation

Sand	50	Shale & Shells	1520
Surface, Sand & Shale	140	Lime & Shale	1695
Shale & Lime	200	Shale & Lime	2270
Lime Shells	335	Lime	2365
Lime	426	Lime & Shale	2922
Anhydrite, Broken	445	Lime	2993
Anhydrite, Brkn & Shale	530	Shale & Lime	3030
Shale, Shells & Gyp	590	Lime	3060
Lime, Shale, Salt	665	Lime & Shale	3114
Lime & Shale	815	Lime & Chert	3147
Shale & Sand	890	Lime & Shale	3310
Lime & Shale	1090	Shale	3387
Shale, Shells & Salt	1295	Shale	3433
		Maquoketa Dolomite	3435 T.D.

TOPS

Miss.	2907
Kind.	3153
Msnr.	3369
Hunt.	3372
Maq. Sh.	3380
Maq. Dol.	3433
T.D.	3435

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 X 1957

CONSERVATION DIVISION
 Wichita, Kansas

Note: Rework - DD to 3441

PLUGGING	
FILE	SEC 35 T 15 R 4 W
BOOK	PAGE 16 LINE 28