

15169-00853.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1964
10-16-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Socony Mobil Oil Company

Complete Address: 300 North Broadway, Wichita, Kansas

Lease Name T. Swenson Well No. 1

Location C SE SE SE Sec. 26 Twp. 15 Rge. 4 (E) (W) X

County Saline Total Depth 3413'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5 PM Day 13 Month October Year 1964

The Above well was plugged as follows:

Hole filled with sand to 3400' and cemented with 5 sacks.

Hole filled with mud to 260'. Rock bridge set from 260' to 250' and

hole cemented with 20 sacks. Hole filled with mud to 40'. Rock bridge

set from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/16/64

INV. NO. 9989-W

Signed: [Signature]
Well Plugging Supervisor