

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19042-00-00
Spot: NENWSE Sec/Twnshp/Rge: 21-14S-19W
2251 feet from S Section Line, 1611 feet from E Section Line
Lease Name: KRAUS Well #: 4
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 215 | 0 | 100 SX |
| PROD | 5.5 | 3742 | 0 | 175 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2011 9:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
Plugging Start milling on well on 08/25/2011 - was at 680'.
Method: Milled for ten days - got to 1070'.
Rods and iron in the hole on 09/08/2011.
LK perforators perfed two shot hole at 425'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2011 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Bowman Oil RIH with tubing to 1046'.
Allied rigged to tubing and pumped 100 sxs 60/40 pozmix - 4% gel to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 200#.
Rigged to 8 5/8" casing and pumped 5 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.


Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #38259.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3
SEP 16 2011 9/20/11

SEP 09 2011

KCC WICHITA