

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20438-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 35-9S-15W
475 feet from S Section Line, 1350 feet from E Section Line
Lease Name: STULL Well #: 1
County: OSBORNE Total Vertical Depth: 3725 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/09/2011 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: TOM Company: PIONEER RESOURCES Phone: (785) 543-5556

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 09/09/2011 11:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:


1st. Plug at 1190' w/25 sxs.
2nd. Plug at 790' w/80 sxs.
3rd. Plug at 265' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
SEP 19 2011

KCC WICHITA

Form CP-2/3

9/20/11

SEP 15 2011