

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20348-00-01
Spot: S2NESESW Sec/Twnshp/Rge: 31-5S-36W
880 feet from S Section Line, 2310 feet from W Section Line
Lease Name: TOVREA Well #: 1
County: RAWLINS Total Vertical Depth: 4642 feet

Operator License No.: 6509
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO
Address: PO BOX 1197
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	391	0	w/unknown sxs cmt
PROD	4.5	4995	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2011 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JIM CLARK Company: CLA-MAR OIL, COMPANY Phone: (785) 623-1700

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 4% gel - 200# hulls - 8 sxs gel.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/12/2011 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 391' w/unknown sxs cement.
4 1/2" production casing set at 4760' w/unknown sxs cement.
TD 4972'. Well was plugged on 11/14/1984 - 1775' of casing recovered.
05/15/1995 - Well was re-entered. 1775' casing set over existing casing with 4 1/2" to 7" swage.
Pumped 400 sxs cement - cement circulated to surface.
Washed down to 4720'. Production casing hole squeezed from 2740' - 3150' with 280 sxs cement.
Perforations: 4665' - 4687'. All other perforations squeezed with cement.
09/12/2011 - Ran tubing to 4630'. Pumped 8 sxs gel followed with 50 sxs cement mixed with 100# hulls.
Pulled tubing to 3100' - pumped 25 sxs cement mixed with 50# hulls.
Pulled tubing to 2275' - pumped 100 sxs cement mixed with 50# hulls.
Pulled tubing to 700' - pumped 55 sxs cement - cement to surface.
Topped 4 1/2" casing with 5 sxs cement - plug complete.

Perfs:

Top	Bot	Thru	Comments
4665	4687		
4552	4555		
4533	4537		
4460	4463		
4421	4425		

Remarks: ALLID CEMENTING COMPANY-TICKET #35983.

Plugged through: CSG

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

RECEIVED
SEP 19 2011
KCC WICHITA

Form CP-2/3

9/20/11

SEP 14 2011