

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-00508-00-01
Spot: NWNWSW Sec/Twnshp/Rge: 14-21S-11W
2445 feet from S Section Line, 284 feet from W Section Line
Lease Name: FAIR EST OWWO Well #: 1-14
County: STAFFORD Total Vertical Depth: 3428 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	231		WITH 200 SX CMT
PROD	4.5	3428	1426	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2011 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3050' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2011 9:40 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3042' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 279' WITH 50 SX CMT. 3RD PLUG AT 39' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3106	3117		LANSING- KC

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
SEP 19 2011

KCC WICHITA

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 16 2011
KCC DODGE CITY

Form CP-2/3
9/20/11