

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-181-20523-00-00
Spot: NWSE Sec/Twnshp/Rge: 4-6S-40W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HOTOVEC Well #: 33-4
County: SHERMAN Total Vertical Depth: 1561 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.

Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	359	0	140 SX CMT 50/50 POZ
PROD	4.5	1529	0	88 SX CMT 32 SX LEAD/ 56 SX TAIL

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/13/2011 9:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: TOM THOMAS Company: NOBLE ENERGY, INC. Phone: (970) 848-0331

Proposed Plugging Method: Ordered 150 sxs Neat Cement and 3 sxs gel. Yield = 1.07 cubic foot/sack.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/13/2011 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

7" surface casing set at 359' w/140 sxs cement.
4 1/2" production casing set at 1529' w/88 sxs cement.
PBTD 1486'. TD 1561'.
Ran tubing to 1400' - pumped 3 sxs gel - followed with 40 sxs cement.
Pulled tubing to 409' - pumped 75 sxs cement - cement to surface.
Pulled tubing to surface. Topped 4 1/2" casing with 5 sxs cement.
7" surface casing full of cement.

Perfs:

Top	Bot	Thru	Comments
1400	1419		NIOBRARA

Remarks: BISON CEMENT COMPANY-TICKET #10468.

Plugged through: TBG

RECEIVED

SEP 19 2011

KCC WICHITA

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

Form CP-2/3

9/20/11

SEP 14 2011