

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22959-00-00
Spot: NWNE Sec/Twnshp/Rge: 7-30S-11W
666 feet from N Section Line, 1890 feet from E Section Line
Lease Name: HOUSE Well #: 1-7
County: BARBER Total Vertical Depth: 3850 feet

Operator License No.: 32192
Op Name: PRIDE ENERGY COMPANY, A GENERA
Address: P O BOX 701950
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	322		WITH 250 SX CMT
DVT		2465		WITH 310 SX CMT
PLG		3791		
PROD	5.5	3839	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2011 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: RUN TBG TO 3733' & 70 SX CMT WITH 200# HULLS MIXED IN. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/14/2011 1:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 3733'. PUMPED 10 SX GEL & 70 SX CMT WITH 100# HULLS MIXED IN. PULLED TBG TO 713'. PUMPED 70 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2". PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2" WITH 30 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 200 PSIG WITH 40 SX CMT. BLEW FITTING OUT OF SURFACE HEAD.

Perfs:

Top	Bot	Thru	Comments
3730	3734		TORONTO
3188	3192		U. TOPEKA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

RECEIVED
SEP 19 2011

KCC WICHITA

District: 01

RECEIVED

SEP 16 2011

KCC DODGE CITY

Signed

Richard M. Lacey

(TECHNICIAN)

Form CP-2/3

a/20/11