

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00789-00-00
Spot: NE Sec/Twnshp/Rge: 36-23S-32W
3985 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MCCLURE Well #: 1-36
County: FINNEY Total Vertical Depth: 2729 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	495		WITH 275 SX CMT
PROD	5.5	2761	0	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2011 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2011 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMPED 100 SX CMT, 150# HULLS, 15 7/8" BALL SEALERS TO 2678'. ESTIMATE TOC # 1600'. TESTED CASING TO 700#. 2ND PLUG RAN BOND LOG. ESTIMATE TOC @ 1415'. PERFORATED CASING AT 887'. CIRCULATED CMT TO SURFACE WITH 205 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2678	2760		UPPER KRIDER

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
SEP - 8 2011
KCC DODGE CITY

RECEIVED
SEP 19 2011
KCC WICHITA

Form 602/3
9/20/11