

15-169-00873-0000⁰²

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 52 R

NW, SEC. 36, T. 15 S., R. 4 W/E

1320 FEET FROM N/S SECTION LINE

467 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5151

LEASE NAME Bengston WELL # 4

OPERATOR: Gear Petroleum Co, Inc.
NAME & ADDRESS 300 Sutton Place
Wichita, Kansas 67202

COUNTY Saline

WELL TOTAL DEPTH 3465 # 112.61 FEET

CONDUCTOR PIPE: SIZE 15 1/2 FEET 103

SURFACE CASING: SIZE 10 3/4 FEET 362

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Operator LICENSE NUMBER 5151

ADDRESS _____

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 13 MONTH: July YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Max Parsons

(COMPANY NAME) Gear Petroleum Co, Inc. (PHONE) 913 628 6904

WERE: Set rock bridge at 500'. Fill 7" casing to base of
cellar with 2 1/2 yards ready-mix concrete. Squeeze 10 3/4"
7" annulus with 75 sacks 50/50 Permox w/4% gel.

PLUGGING PROPOSAL RECEIVED BY [Signature]
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:15 AM DAY: 13 MONTH: July YEAR: 1983

ACTUAL PLUGGING REPORT Same as above

REMARKS: A. J.'s Quality Concrete Ticket # 013494
Allied Cementing Co, Inc. Ticket # 35608
No casing recovered.

RECEIVED
STATE CORPORATION COMMISSION
7-19-83
JUL 19 1983
CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED [Signature]
(TECHNICIAN)

INVOICED
DATE 7-25-83
INV. NO. 4932-W

FORM CP-2/3
REV. 6-83