

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00299-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 29-18S-2W
2947 feet from S Section Line, 4705 feet from E Section Line
Lease Name: ALEXANDER Well #: 104029
County: MCPHERSON Total Vertical Depth: 3233 feet

Operator License No.: 6753
Op Name: ALEXANDER, JESSE R.
Address: 200 N. LAKESIDE DR.
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	140		140 SX
PROD 5		2385	800	50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2011 11:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: _____ Company: MIKES TESTING & SALVAGE Phone: _____

Proposed Plugging Method: PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: _____

Witness Type: NONE

Date/Time Plugging Completed: 09/14/2011 11:30 AM

KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

KELSO'S LAID OUT WELL AND CHECKED BOTTOM. THEY THEN SANDED OFF BOTTOM. TAGGED SAND @ APPROX 2240' AND CAPPED W/5SX. THEY THEN PULLED STRETCH AND RIPPED CASING @ 800'. 9/13/11 KELSO'S PULLED CASING UP TO 400' AND COPELAND TIED ON AND CIRCULATED 305 SXS 60/40 POS W/4% GEL. COPELAND TK #37772. THEY DID NOT GET GOOD RETURNS. 9/14/11 COPELAND BACK OUT RAN POLY PIPE DOWN AND TAGGED CEMENT @ 175'. COPELAND CIRCULATED CEMENT TO SURFACE USED 75 SX 60/40 POS W/4% GEL TK #37773. 9/16/11 I CHECKED TOP PLUG AND FOUND IT @ SURFACE.

Top	Bot	Thru	Comments
2327	2338	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

Form CP-2/3

SEP 26 2011

9/27/11

KCC WICHITA

12K