

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00926-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 20-1S-18W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAGEMAN A Well #: 2
County: PHILLIPS Total Vertical Depth: 3450 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	190	0	175 SX
PROD	5.5	3448	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2011 10:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tubing and rods stuck in the hole at 2850'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2011 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2800' - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1400' - pumped 135 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 50 sxs 60/40 pozmix - 4% gel. No pressure.

Perfs:

Top	Bot	Thru	Comments
3391	3395		
3371	3375		
3357	3361		

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38287.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

9/27/11

SEP 21 2011