

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30218-00-00
Spot: N2NENWNW Sec/Twnshp/Rge: 31-14S-14W
330 feet from N Section Line, 4290 feet from E Section Line
Lease Name: HUMMEL Well #: 4
County: RUSSELL Total Vertical Depth: 3175 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 605 | 0 | 300 SX |
| PROD | 5.5 | 3164 | 0 | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2011 10:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: BEREXCO, LLC Company: DENNIS KIRMER Phone: (785) 628-6101

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 300# hulls.
Perf: 780' - 350'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2011 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

09/14/2011 - Sanded off open hole to 3120'. (Tagged by Allied Cementing)
09/16/2011 - Ran tubing to 2535' - pumped 50 sxs cement - followed with 50 sxs cement with 150# hulls.
Pulled tubing to 1400' - pumped 40 sxs cement with 100# hulls.
POOH. Perforated at 350' and 780'.
Ran tubing to 840' - pumped 80 sxs cement - cement circulated - closed backside valve and pumped 55 sxs cement.
Max. P.S.I. 500#. Circulated cement out the Braden head - closed Braden head valve.
POOH. Topped off well with 15 sxs cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3164 | 3175 | | |
| 3115 | 3119 | | |
| 3088 | 3092 | | |
| 3068 | 3071 | | |
| 3008 | 3011 | | |
| 2954 | 2957 | | |
| 2931 | 2934 | | |
| 2898 | 2900 | | |
| 2826 | 2829 | | |

RECEIVED
SEP 23 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38264.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

9/27/11

SEP 19 2011