



15-16 9.00 851-0000

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

January 29, 1963

RECEIVED  
 STATE CORPORATION COMMISSION

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

FEB 4 1963  
 2-4-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Co.

Complete Address: Box 405, Chase, Kansas

Lease Name: Swenson Well No. 7

Location: SW SW NE Sec. 25 Twp. 15 Rge. 4 (E) (W) X

County Saline Total Depth 3427' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement with 20 sacks. Fill hole with mud

to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

*Albert J. Lomax*  
 Conservation Division Agent