



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 19 1963
 2-19-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Co.

Complete Address: Box 405, Chase, Kansas

Lease Name: Swenson Well No. 85

Location: SW NW NE Sec. 25 Twp. 15 Rge. 4 (E) (W) X

County Saline Total Depth 3414' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 3 sacks.

Fill hole with mud to 210'. Set rock bridge from 210'

to 200' and cement with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

[Signature]
 Conservation Division Agent