

State of Kansas



15:169.00857.0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ, Commissioner  
HARRY G. WILES, Commissioner  
RAYMOND B. HARVEY, Secretary  
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

January 13, 1965

RECEIVED  
STATE CORPORATION COMMISSION

FEB 8 1965  
2-8-65

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc. <sup>Wichita, Kansas</sup>

date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name: Oberg Well No. 3

Location: NE NE NE <sup>1000</sup> Sec. 35 Twp. 15 Rge. 4 NE (W) X

County Saline Total Depth 3422' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pully was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 3 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to

250' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with

10 sacks cement.

Very truly yours,

Conservation Division Agent