

State of Kansas



15:169:00858:0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 4, 1965

RECEIVED  
STATE CORPORATION COMMISSION

FEB 15 1965  
2-15-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc this

date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Socony Mobil Oil Company

Complete Address: 300 North Broadway, Wichita, Kansas

Lease Name: Oberg Well No. 4

Location: NE SW NE Sec. 35 Twp. 15 Rge. 4 (X) (W) X

County Saline Total Depth 3423 Oil Well

Gas Well      Input Well X SWD Well      D & A      Lost Hole     

Mr. Pully was instructed to plug the well as follows:

Fill hole with sand to 3410' and cement with 5 sacks.  
Fill hole with mud to 270'. Set rock bridge from 270' to  
260' and cement hole with 20 sacks. Fill hole with mud to  
40'. Set rock bridge from 40' to 30' and cap hole with 10  
sacks cement.

Very truly yours,

[Signature]  
Conservation Division Agent