



15:169:00865:0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 10, 1965

RECEIVED  
STATE CORPORATION COMMISSION

FEB 18 1965  
2-18-65

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling Inc. this

date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Socony Mobil Oil Company

Complete Address: 300 N. Broadway, Wichita, Kansas.

Lease Name: Oberg Well No. 5

Location: Approx. C E 1/2 NE Sec. 35 Twp. 15 Rgs. 4 (E) (W)  (X)

County Saline Total Depth 3472' Oil Well  (X)

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Pully was instructed to plug the well as follows:

Fill hole with sand to 3400' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to

250' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with 10

sacks cement.

Very truly yours,

Conservation Division Agent