

State of Kansas



15:167 00106:0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 28, 1965

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1965
1-28-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling, Inc. this
date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Socony Mobil Oil Company

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name: Oberg Well No. 1

Location: NE NE NE Sec. 35 Twp. 15 Rge. 4 (W) (X)

County Saline Total Depth 3416' Oil Well (X)

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

- Fill hole with sand to 3400' and cement with 5 sacks.
- Fill hole with mud to 260'. Set rock bridge from 260' to
- 250' and cement hole with 20 sacks. Fill hole with mud
- to 40'. Set rock bridge from 40' to 30' and cap hole with
- 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent