

State of Kansas



15:169-00498-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 23 1966
5-23-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply, Inc.

Complete Address: P.O. Box 302, Russell, Kansas

Lease Name: Liljestrang Well No. 2

Location: SW SE SE Sec. 35 Twp. 15 Rge. 4 CE (W) X

County Saline Total Depth 3461' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 4 1/2" plug to 3430'. Fill hole with sand to 3420' and cement hole with 3 sacks. Fill hole with mud to 260'. Set rock bridge from 260' to 250' and cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent