



15-169-00497-002

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

May 11, 1966

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1966  
5-18-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Fender Pipe & Supply, Inc.

Complete Address: P.O. Box 302, Russell, Kansas

Lease Name: Liljestrاند Well No. 1

Location: SE SE SE Sec. 35 Twp. 15 Rge. 4 (E)(W) X

County Saline Total Depth 3437' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3425' and cement with 3 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent