

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

8- December 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Eves of Midwest Casing Pulling Service has this

date requested permission to plug the following described well:

Operator's Full Name: Calvin Exploration, Inc.

Complete Address: Box 6 Liberal Kansas 67901

Lease Name: Novingers Well No. 1-25

Location: N 1/2 Sec. 25 Twp. 33S Rge. 30W (E) (W)

County: Meade Total Depth: 5915'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Eves was instructed to plug the well as follows:

There is 1518' of 8 3/8" surface casing cement circulated. There is 5915'
of 4 1/2" production pipe cemented with 175 lbs. bond lag on cement was at 5494'.
They plugged back to 5870' to. The perforations were from 5796' to 5804'.
1st plug pumped to bottom with 1 sbx. shells + 15 sbx. of cement. 2nd
plug at 1500' with 35 sbx. of cement. 3rd plug 40' to 50' on solid bridge
with 10 sbx. of cement. Plugging accomplished by midwest
casing pulling service.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

DEC 1 1 1981

Paul Luthi
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas