

15-119-20409-00-00

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-119-20409-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Calvin Exploration, Inc.

Complete Address Box 6 Liberal Kansas 67901

Lease Name Woringer Well No. 1-25

Location 2540' ENL & 900' FWL NW Sec. 25 Twp. 33S Rge. 30W (East) (West)

County Meade Total Depth 5915'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling Service

Address Box F Sublette Kansas 67877 License No. 766

Operation Completed: Hour: 3:30 PM Day: 10 Month: December Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

*There is 1518' of 8 3/8" surface casing cement circulated. There is 5915' of 4 1/2" production pipe cemented with 175 lbs of cement, bond log on cement was at 5494'. They plugged back to 5870'. The perforations were from 5796' to 5804'. 1st plug pumped to bottom with 1 lb of hulls & 15 lbs of cement. 2nd plug at 1500' with 35 lbs of cement. 3rd plug 40' to 0' on solid bridge with 10 lbs of cement. Plugging accomplished by Midwest casing pulling service. They recovered \_\_\_\_\_ of 4 1/2" production pipe.*

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

DEC 11 1981

Signed: Paul Luthi  
Conservation Division Agent

DATE 1-19-82  
INV. NO. 8908 W  
CONSERVATION DIVISION  
Wichita, Kansas

15-119-20409-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado, Derby Bldg.  
Wichita, Kansas 67202-1286

## INVOICE and WELL PLUGGING AUTHORITY

January 19, 1982INVOICE NUMBER: 8958-WTO: Calvin Explorations1125 Seventeenth<sup>o</sup> Ste. 2000Denver. Colo. 80202PLUGGING ASSESSMENT AS FOLLOWS: **PAYABLE UPON RECEIPT**

Novinger 1-25

2540' FNL &amp; 900' FWL NW Sec 25-33-30W

Meade

5915'

\$192.24

NOTE: We also need the following before our file is completed:


- Well Plugging Record (CP-4)  
 Well Log  
 Well Plugging Application (CP-1)

## WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.




---

 Administrator

---

 Mr. Paul Luthi Box 495 Minneola Kansas 67112 (316) 885-4838
 

---

is hereby assigned to supervise the plugging of the above mentioned well.