

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00667-00-01
Spot: NWSENE Sec/Twnshp/Rge: 27-17S-13W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: BOGER Well #: 3
County: BARTON Total Vertical Depth: 3416 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	310	0	100 SX
PROD	4.5	3412	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2011 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM COMPANY Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Bad casing at 2450' - ran outside casing - will plug from there.
Ran tubing to 2450' - pumped 100 sxs cement.
Pulled tubing to 1450' - pumped 75 sxs cement - circulated to surface.
Pulled tubing - tied onto casing - pumped 10 sxs cement.
Max. P.S.I. 500#. Shut in.
Tied to surface pipe - pumped 15 sxs cement.
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3372	3383		ARBUCKLE
3176	3205		LANSING
3135	3140		LANSING
2970	2980		TOPEKA

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

RECEIVED

Form CP-2/3

OCT 03 2011

KCC WICHITA

SEP 27 2011