

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04345-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 4-18S-14W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: FRIEB Well #: 4
County: BARTON Total Vertical Depth: 3452 feet

Operator License No.: 4323
Op Name: REICHLINGER, GARY DBA REICHLING
Address: 118 W 8TH ST PO BOX 4
YORK, NE 68467

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	741	0	325 SX
COND	13.37	218	0	200 SX
PROD	7	3446	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2011 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GARY REICHLINGER Company: REICHLINGER BUSINESS SERVICE Phone: (402) 362-4191

Proposed Plugging Method: Ordered 511 sxs 60/40 pozmix - 4% gel - 600# hulls - 18 sxs gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2011 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs at 1600' - 950' - 400'.
Ran tubing to 3000' - pumped 18 sxs gel - followed with 75 sxs cement with 200# hulls.
Pulled tubing to 1600' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 950' - pumped 75 sxs cement with 200# hulls.
Pulled tubing - circulated cement to surface with 60 sxs cement.
Pulled tubing - tied onto casing - pumped 75 sxs cement - circulated out surface pipe.
Shut in.

Perfs:

Top	Bot	Thru	Comments
3446	3452		ARBUCKLE
3232	3236		LKC-B
3204	3208		LKC-A

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED

OCT 03 2011

KCC WICHITA

SEP 27 2011

Form CP-2/3