

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07003-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 25-14S-14W
330 feet from N Section Line, 1980 feet from E Section Line
Lease Name: STRECKER B Well #: 1
County: RUSSELL Total Vertical Depth: 2914 feet

Operator License No.: 6627
Op Name: PROSPECT OIL & GAS CORP
Address: PO BOX 837
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	743	0	w/unknown sxs cmt
PROD	5.5	2874	920	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2011 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK KILIAN Company: PROSPECT OIL & GAS CORP Phone: (785) 483-6266

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shot casing at 1000' - cut casing at 920' - leaving 1954' of 5 1/2" casing in the hole.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2011 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

09/16/2011 - Sanded casing off.
09/19/2011 - cut casing at 920' - pulled tubing to 910' - pumped 120 sxs cement with 300# hulls.
Pulled tubing to 380' - pumped 50 sxs cement with 50# hulls.
Pulled casing to 120' - pumped 30 sxs cement - cement circulated.
POOH. Cellar was full of cement.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKETR #5335.

Plugged through: CSG

District: 04

Signed

R. AD. KD

(TECHNICIAN)

CM

RECEIVED

OCT 03 2011

Form CP-2/3

SEP 22 2011

KCC WICHITA