

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22368-00-00
Spot: S2NWNW Sec/Twnshp/Rge: 4-15S-18W
4330 feet from S Section Line, 4642 feet from E Section Line
Lease Name: OLDHAM Well #: 4
County: ELLIS Total Vertical Depth: 3900 feet

Operator License No.: 33625
Op Name: HERTEL OIL COMPANY LLC
Address: 704 E 12TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207	0	w/125 sxs cmt
T1	2	3714		
PROD	4.5	3714	0	w/500 sxs cmt

Well Type: SWD UIC Docket No: D20214.0 Date/Time to Plug: 09/13/2011 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GLENN DINKEL Company: HERTEL OIL COMPANY LLC Phone: (785) 628-2445

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV at 1700' - circulate to surface.
Casing leaks 1700' - 2300'.
Shot off fiberglass tubing at 2390'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/13/2011 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2314'.
Allied rigged to tubing - pumped 75 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1146'. Allied rigged to tubing - pumped 75 sxs cement with 250# hulls to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 10 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Rigged to 8 5/8" casing and pumped 5 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.


Perfs:

Top	Bot	Thru	Comments
3714	3724	OH	

Remarks: ALLIED CEMENTING COMPANY-TICKET #35811.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN) CM

SEP 15 2011

RECEIVED Form CP-2/3
OCT 03 2011 cc to MIC
10/04/11
KCC WICHITA