

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21097-00-00
Spot: NWNE Sec/Twnshp/Rge: 32-24S-18W
4636 feet from S Section Line, 1978 feet from E Section Line
Lease Name: SLENTZ Well #: 1-32
County: EDWARDS Total Vertical Depth: 4685 feet

Operator License No.: 9971
Op Name: KODIAK PETROLEUM, INC.
Address: PO BOX 4677
ENGLEWOOD, CO 80155

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4566		
SURF	8.625	290		WITH 200 SX CMT
PROD	4.5	4684	2040	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/19/2011 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 1320' & 4 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 500' WITH 50 SX CMT. PLUG AT 330 WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2011 11:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4210' & 4 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 1220' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 518' WITH 50 SX CMT. 3RD PLUG AT 342' WITH 50 SX CMT. 4TH PLUG AT 41' WITH 23.5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4592	4597		KINDERHOOK
4513	4518		CHEROKEE
4392	4398		MARMATON
4373	4382		MARMATON

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
SEP 21 2011
KCC DODGE CITY

RECEIVED
OCT 03 2011

KCC WICHITA